
- D. Cabinet hardware –Hidden: Review proposals with SHSU Project Representative.
- E. Pre-finished woodwork/In-field finish: Provide pre-finished woodwork where possible. Where in-field finish must be performed, coordinate environmental concerns, ventilation requirements, shutdowns, etc. with SHSU Office of Environmental Health and Safety.
- F. Delivery of woodwork to project: Any area where woodwork is to be installed shall have been satisfactorily conditioned for temperature and humidity control prior to introducing woodwork into the space.

PART 2: PRODUCTS – NOT USED

PART 3: EXECUTION – NOT USED

END OF STANDARD 06402