

General Information

Brick

Brick masonry to be designed and constructed per the standards of the Brick Industry Association.

1.03 Quality Control

- A. Campus brick: SHSU campus has a standard range of colors for selection of the campus brick. The palette of brick colors listed in Products shall be used to create the brick blend for each new building. All brick must meet master plan requirements.
- B. Grout: Coordinate color of mortar with the SHSU project representative. Use only a pre-mixed mortar, with no color.

ade SW.

In the drawings the A/E will provide a detail that indicates the size of the brick-work panel that will also contain all exterior materials such as stone, cast stone, curtain wall, glazing, sealants, etc. for final approval of brick color as well as all exterior colors for the project.

The A/E shall require, in the Project's Specification along with a detail in the drawings, that prior to ordering brick, the Contractor shall erect a 300 brick sample panel in mortar, all as specified, at the jobsite for final approval consideration by the Director of Project Delivery or designee.

The approved panel shall remain on the jobsite as a visual criterion which the final construction must match.

Expansion joints and control joints in masonry veneer walls shall be appropriately detailed and shown on building elevations. Extra precautions shall be taken at Sam Houston State University due to extreme summer temperatures.

